



Alacrity Solutions Commercial Services Division

9725 Windermere Drive
Fishers, IN 46037

Insured: City of Oberlin
Property: 201 S. Rodehaver Avenue
Oberlin, KS 67749

Claim Rep.: Kelly Kaiser
Business: 245 N. Waco Ste. 330
Wichita, KS 67202

Business: (316) 352-5832
E-mail: kelly.j.kaiser@emcins.com

Estimator: Scott Bradley

Business: (314) 803-6341
E-mail: scott.
bradley@alacritysolutions.
com

Claim Number: 1730956

Policy Number: 6A3-07-02---23

Type of Loss: Hail

Date of Loss: 6/7/2022 7:15 PM
Date Inspected:

Date Received: 6/10/2022 7:15 PM
Date Entered: 6/12/2022 7:13 PM

Price List: KSKS8X_JUN22
Restoration/Service/Remodel
Estimate: OBERLIN-LOC23-BLDG-1

This is an estimate of observed damage only. This is not an authorization of repair, nor is it a guarantee of payment. Your policy may contain provisions that could change the amount. The Insurer assumes no responsibility for any repair performance.



Alacrity Solutions Commercial Services Division


9725 Windermere Drive
Fishers, IN 46037

OBERLIN-LOC23-BLDG-1

General Items

QUANTITY	TAX	RCV	AGE/LIFE	COND.	DEP %	DEPREC.	ACV
28. Dumpster load - Approx. 40 yards, 7-8 tons of debris 1.00 EA							
Dumpster size needed for bulkiness of siding, not weight.							

Totals: General Items



Right Elevation (North)

Formula Elevation 100' x 17' 6" x 0"

1750.00 SF Walls	100.00 LF Floor Perimeter
1750.00 SF Long Wall	1750.00 SF Short Wall
100.00 LF Ceil. Perimeter	


QUANTITY	TAX	RCV	AGE/LIFE	COND.	DEP %	DEPREC.	ACV
1. Remove Wall/roof panel - ribbed - 26 gauge - up to 1" 1,750.00 SF							
3. Wall/roof panel - ribbed - 26 gauge - up to 1" 1,750.00 SF							
4. Remove Metal outside corner post 35.00 LF							
7. Remove Metal J trim - metal building 39.00 LF							
8. Metal J trim - metal building 39.00 LF							
9. Remove Window screen, 1 - 9 SF 2.00 EA							
12. Window screen, 1 - 9 SF 2.00 EA							
13. Remove Exterior door - metal - insulated - flush or panel style 1.00 EA							
15. Exterior door - metal - insulated - flush or panel style 1.00 EA							
16. Door knob/lockset - Detach & reset 1.00 EA							

Totals: Right Elevation (North)



Alacrity Solutions Commercial Services Division

9725 Windermere Drive
Fishers, IN 46037



Rear Elevation (West)

Formula Elevation 52' x 17' 6" x 7'

1092.00 SF Walls
1092.00 SF Long Wall
53.85 LF Ceil. Perimeter

52.00 LF Floor Perimeter
1092.00 SF Short Wall

QUANTITY	TAX	RCV	AGE/LIFE	COND.	DEP %	DEPREC.	ACV
18. Remove Window screen, 1 - 9 SF 1.00 EA							
19. Window screen, 1 - 9 SF 1.00 EA							
20. Remove Wall/roof panel - ribbed - 26 gauge - up to 1" 1,092.00 SF							
21. Wall/roof panel - ribbed - 26 gauge - up to 1" 1,092.00 SF							
22. Remove Metal outside corner post 17.50 LF							
23. Remove Metal J trim - metal building 9.00 LF							
24. Metal J trim - metal building 9.00 LF							
25. Meter mast for overhead power - Detach & reset 1.00 EA							
To allow for siding replacement.							

Totals: Rear Elevation (West)

Line Item Totals: OBERLIN-LOC23-
BLDG-1



Alacrity Solutions Commercial Services Division

9725 Windermere Drive
Fishers, IN 46037

Grand Total Areas:

2,842.00	SF Walls	0.00	SF Ceiling	2,842.00	SF Walls and Ceiling
0.00	SF Floor	0.00	SY Flooring	152.00	LF Floor Perimeter
2,842.00	SF Long Wall	2,842.00	SF Short Wall	153.85	LF Ceil. Perimeter
0.00	Floor Area	0.00	Total Area	0.00	Interior Wall Area
0.00	Exterior Wall Area	0.00	Exterior Perimeter of Walls		
0.00	Surface Area	0.00	Number of Squares	0.00	Total Perimeter Length
0.00	Total Ridge Length	0.00	Total Hip Length		