



Alacrity Solutions Commercial Services Division

9725 Windermere Drive
Fishers, IN 46037

Insured: City of Oberlin
Property: 101 W. Commercial Street
Oberlin, KS 67749

Claim Rep.: Kelly Kaiser
Business: 245 N. Waco Ste. 330
Wichita, KS 67202

Business: (316) 352-5832
E-mail: kelly.j.kaiser@emcins.com

Estimator: Scott Bradley

Business: (314) 803-6341
E-mail: scott.
bradley@alacritysolutions.
com

Claim Number: 1730956

Policy Number: 6A3-07-02---23

Type of Loss: Hail

Date of Loss: 6/7/2022 7:15 PM
Date Inspected:

Date Received: 6/10/2022 7:15 PM
Date Entered: 6/12/2022 7:13 PM

Price List: KSKS8X_JUN22
Restoration/Service/Remodel
Estimate: OBERLIN-LOC9-BLDG-1

This is an estimate of observed damage only. This is not an authorization of repair, nor is it a guarantee of payment. Your policy may contain provisions that could change the amount. The Insurer assumes no responsibility for any repair performance.


OBERLIN-LOC9-BLDG-1

General Items

QUANTITY	TAX	RCV	AGE/LIFE	COND.	DEP %	DEPREC.	ACV
----------	-----	-----	----------	-------	-------	---------	-----

Totals: General Items

Roof




Roof1 Large Octagon

485.46	Surface Area	4.85	Number of Squares
101.44	Total Perimeter Length		
58.07	Total Hip Length		

QUANTITY	TAX	RCV	AGE/LIFE	COND.	DEP %	DEPREC.	ACV
----------	-----	-----	----------	-------	-------	---------	-----

- 7. Roofing felt - 15 lb.
4.85 SQ
- 8. Laminated - comp. shingle rfg. - w/out felt
5.67 SQ
- 13. Asphalt starter - universal starter course
79.00 LF
- 14. Ridge cap - composition shingles
87.00 LF

Totals: Roof1 Large Octagon



Roof2 Small Octagon

50.44	Surface Area	0.50	Number of Squares
51.22	Total Perimeter Length		
5.13	Total Hip Length		



Alacrity Solutions Commercial Services Division

9725 Windermere Drive
Fishers, IN 46037

	QUANTITY	TAX	RCV	AGE/LIFE	COND.	DEP %	DEPREC.	ACV
2. Remove Weathervane - copper	1.00 EA							
5. Weathervane - copper	1.00 EA							
9. Tear off, haul and dispose of comp. shingles - Laminated	0.50 SQ							
10. Roofing felt - 15 lb.	0.50 SQ							
11. Laminated - comp. shingle rfg. - w/out felt	1.00 SQ							
12. Asphalt starter - universal starter course	18.00 LF							
15. Ridge cap - composition shingles	24.00 LF							

Totals: Roof2 Small Octagon

Total: Roof

**Line Item Totals: OBERLIN-LOC9-
BLDG-1****Grand Total Areas:**

0.00 SF Walls	0.00 SF Ceiling	0.00 SF Walls and Ceiling
0.00 SF Floor	0.00 SY Flooring	0.00 LF Floor Perimeter
0.00 SF Long Wall	0.00 SF Short Wall	0.00 LF Ceil. Perimeter
0.00 Floor Area	0.00 Total Area	0.00 Interior Wall Area
288.91 Exterior Wall Area	0.00 Exterior Perimeter of Walls	
535.90 Surface Area	5.36 Number of Squares	152.66 Total Perimeter Length
0.00 Total Ridge Length	63.20 Total Hip Length	